

Appendix 13.11-C Stage-Storage Relationships

Tenas Project – Water Management Design Technical Report
Appendix A: Stage-Storage-Elevation Relationships

Table A- 1: Management Pond Stage-Storage-Elevation Relationships

Elevation [masl]	Cumulative volumes [m3]			Surface Area [m2]		
	North MP	East MP	West MP	North MP	East MP	West MP
753.0	-	-	1	-	-	-
753.5	-	-	158	-	-	-
754.0	-	-	906	-	-	-
754.5	-	-	2,332	-	-	3,085
755.0	-	-	4,404	-	-	4,363
755.5	-	-	7,105	-	-	5,670
756.0	-	-	10,512	-	-	7,150
756.5	-	-	14,868	-	-	9,240
757.0	-	-	20,458	-	-	11,650
757.5	-	-	27,329	-	-	14,210
758.0	-	-	36,011	-	-	16,740
758.5	-	-	46,879	-	-	22,650
759.0	-	-	59,579	-	-	26,000
759.5	-	-	73,865	-	-	29,350
760.0	-	-	89,696	-	-	32,330
760.5	-	-	106,984	-	-	35,040
761.0	-	-	125,555	-	-	37,650
761.5	-	-	145,444	-	-	40,240
762.0	-	-	166,661	-	-	42,880
762.5	-	-	189,282	-	-	45,680
763.0	-	-	213,354	-	-	48,560
763.5	-	-	238,832	-	-	51,300
764.0	-	-	265,706	-	-	54,100
764.5	-	-	293,983	-	-	56,800
765.0	-	-	323,643	-	-	59,500
765.5	-	-	354,661	-	-	62,100
766.0	-	-	387,023	-	-	64,800
766.5	-	-	420,676	-	-	67,200
767.0	-	-	455,502	-	-	69,500
767.5	-	-	491,462	-	-	71,700
768.0	-	-	528,531	-	-	74,000
768.5	-	-	566,688	-	-	76,100
769.0	-	-	605,936	-	-	78,300
769.5	-	-	646,276	-	-	81,900
770.0	-	-	687,695	-	-	85,500
770.5	-	-	730,173	-	-	87,900
771.0	-	-	773,697	-	-	90,100
771.5	-	-	818,248	-	-	92,100
772.0	-	-	863,781	-	-	94,100

Tenas Project – Water Management Design Technical Report

Appendix A: Stage-Storage-Elevation Relationships

Elevation [masl]	Cumulative volumes [m3]			Surface Area [m2]		
	North MP	East MP	West MP	North MP	East MP	West MP
772.5	-	-	910,295	-	-	96,100
773.0	-	-	957,801	-	-	98,200
773.5	-	-	1,006,315	-	-	100,200
774.0	-	-	1,055,844	-	-	102,300
774.5	-	-	1,106,399	-	-	104,400
775.0	-	-	1,157,984	-	-	106,500
775.5	-	-	1,210,602	-	-	108,700
776.0	-	-	1,264,266	-	-	110,800
776.5	-	-	1,322,177	-	-	113,000
777.0	-	-	1,381,203	-	-	115,100
777.5	-	-	1,441,272	-	-	117,100
778.0	-	-	1,502,357	-	-	119,100
778.5	-	-	1,564,448	-	-	121,100
779.0	-	-	1,627,554	-	-	123,100
779.5	-	-	1,691,688	-	-	125,100
780.0	-	-	1,756,845	-	-	127,100
780.5	-	-	1,823,031	-	-	129,100
781.0	-	-	1,890,246	-	-	131,100
781.5	-	-	1,958,490	-	-	133,200
782.0	-	-	2,027,767	-	-	135,200
782.5	-	-	2,098,078	-	-	137,200
783.0	-	-	2,169,433	-	-	139,200
783.5	-	-	2,241,912	-	-	141,500
784.0	-	-	2,315,618	-	-	143,900
784.5	-	-	2,390,689	-	-	146,900
785.0	-	-	2,467,148	-	-	149,600
785.5	-	-	2,545,068	-	-	152,600
786.0	-	-	2,624,532	-	-	155,600
786.5	-	-	2,705,621	-	-	158,900
787.0	-	-	2,788,365	-	-	162,200
787.5	-	-	2,872,732	-	-	165,300
788.0	-	-	2,958,701	-	-	168,500
788.5	-	-	3,046,286	-	-	171,800
789.0	-	-	3,135,510	-	-	175,100
789.5	-	-	3,226,391	-	-	181,100
790.0	-	-	3,319,017	-	-	186,900
790.5	-	-	3,413,568	-	-	191,000
791.0	-	-	3,510,406	-	-	194,800
791.5	-	-	3,609,548	-	-	201,700
792.0	-	-	3,711,020	-	-	206,800
792.5	-	-	3,815,026	-	-	212,700

Tenas Project – Water Management Design Technical Report

Appendix A: Stage-Storage-Elevation Relationships

Elevation [masl]	Cumulative volumes [m3]			Surface Area [m2]		
	North MP	East MP	West MP	North MP	East MP	West MP
793.0	-	-	3,921,701	-	-	218,000
793.5	-	-	4,030,771	-	-	222,300
794.0	-	-	4,141,625	-	-	225,700
794.5	-	-	4,254,107	-	-	229,000
795.0	-	-	4,368,103	-	-	232,000
795.5	-	-	4,483,523	-	-	234,800
796.0	-	-	4,599,998	-	-	236,900
796.5	-	-	4,717,374	-	-	238,800
797.0	-	-	4,835,632	-	-	240,600
797.5	-	-	4,954,783	-	-	242,300
798.0	-	-	5,075,065	-	-	244,000
798.5	-	-	5,196,508	-	-	246,700
799.0	-	-	5,319,055	-	-	248,700
799.5	-	-	5,442,668	-	-	250,600
800.0	-	-	5,567,360	-	-	252,500
800.5	-	-	5,703,541	-	-	254,500
801.0	-	-	5,840,754	-	-	256,400
801.5	-	-	5,978,984	-	-	258,400
802.0	-	-	6,118,222	-	-	260,300
802.5	-	-	6,258,458	-	-	262,200
803.0	-	-	6,399,688	-	-	264,200
803.5	-	-	6,541,941	-	-	266,300
804.0	-	-	6,685,320	-	-	268,400
804.5	-	-	6,829,891	-	-	271,000
805.0	-	-	6,975,848	-	-	273,400
805.5	-	-	7,123,275	-	-	276,200
806.0	-	-	7,272,139	-	-	278,700
806.5	-	-	7,422,418	-	-	281,400
807.0	-	-	7,574,057	-	-	283,900
807.5	-	-	7,727,015	-	-	286,500
808.0	-	-	7,881,221	-	-	288,900
808.5	-	-	8,036,607	-	-	291,100
809.0	-	-	8,193,067	1,623	-	293,400
809.5	466	-	8,350,557	3,093	-	301,900
810.0	1,123	-	8,509,021	5,470	-	310,200
810.5	6,738	-	8,668,394	12,480	-	313,600
811.0	14,942	-	8,828,629	20,760	-	315,500
811.5	25,958	-	8,989,676	37,090	-	317,100
812.0	40,193	-	9,151,508	59,600	-	318,500
812.5	76,609	-	9,322,278	72,200	-	319,900
813.0	118,602	-	9,493,790	85,900	-	321,300

Tenas Project – Water Management Design Technical Report

Appendix A: Stage-Storage-Elevation Relationships

Elevation [masl]	Cumulative volumes [m3]			Surface Area [m2]		
	North MP	East MP	West MP	North MP	East MP	West MP
813.5	166,062	-	9,666,027	97,600	-	322,700
814.0	218,864	-	9,838,972	112,400	-	323,900
814.5	282,474	-	10,012,613	127,800	-	325,200
815.0	350,375	-	10,186,927	140,500	-	326,500
815.5	422,631	-	10,361,900	152,100	-	327,800
816.0	499,164	-	10,537,565	160,600	-	329,100
816.5	583,548	-	10,713,986	169,400	-	330,700
817.0	671,440	-	10,891,236	180,300	-	332,300
817.5	763,219	-	11,069,348	191,700	-	333,900
818.0	859,037	-	11,248,364	201,200	-	335,600
818.5	965,501	-	11,428,354	211,800	-	337,600
819.0	1,076,237	-	11,609,434	224,100	-	339,900
819.5	1,190,980	-	11,791,627	234,400	-	342,500
820.0	1,309,466	-	11,974,937	241,900	-	346,000
820.5	1,434,190	42	12,159,426	249,100	337	351,000
821.0	1,561,375	320	12,345,385	255,800	1,451	359,400
821.5	1,690,649	1,051	12,533,323	259,400	3,827	368,800
822.0	1,821,642	2,547	12,724,378	262,100	8,610	378,000
822.5	1,953,991	10,772	12,920,878	264,600	16,980	389,400
823.0	2,087,586	23,020	13,121,001	267,100	28,270	398,200
823.5	2,222,431	42,014	13,325,122	269,600	47,530	407,200
824.0	2,358,531	69,014	13,533,487	272,100	66,400	421,800
824.5	2,495,890	108,864	13,773,078	274,600	83,200	432,700
825.0	2,634,515	155,702	14,017,326	277,100	101,600	444,900
825.5	2,774,409	209,671	14,266,365	279,600	118,300	456,600
826.0	2,915,579	270,911	14,520,354	282,200	133,200	468,200
826.5	3,058,027	343,147	14,782,602	284,700	147,800	479,000
827.0	3,201,761	422,036	15,049,146	287,300	163,100	490,400
827.5	3,346,783	507,460	15,320,163	289,900	177,800	501,000
828.0	3,493,100	599,289	15,595,810	292,400	192,400	513,000
828.5	3,640,717	703,243	15,879,423	295,000	208,400	527,000
829.0	3,789,638	813,949	16,167,983	297,600	224,300	541,000
829.5	3,939,867	931,380	16,461,317	300,200	241,100	564,000
830.0	4,091,411	1,055,505	16,759,159	304,100	258,100	587,000
830.5	4,091,411	1,192,641	17,063,436	304,100	275,600	600,000
831.0	4,091,411	1,336,892	17,372,266	304,100	295,200	613,000
831.5	4,091,411	1,488,259	17,685,485	304,100	314,000	626,000
832.0	4,091,411	1,646,749	18,003,104	304,100	332,600	638,000
832.5	4,091,411	1,824,665	18,325,865	304,100	354,900	649,000
833.0	4,091,411	2,011,258	18,653,252	304,100	384,600	660,000
833.5	4,091,411	2,206,866	18,985,405	304,100	406,100	671,000

Tenas Project – Water Management Design Technical Report
Appendix A: Stage-Storage-Elevation Relationships

Elevation [masl]	Cumulative volumes [m3]			Surface Area [m2]		
	North MP	East MP	West MP	North MP	East MP	West MP
834.0	4,091,411	2,411,944	19,322,219	304,100	426,200	682,000
834.5	4,091,411	2,638,892	19,664,854	304,100	453,800	694,000
835.0	4,091,411	2,875,363	20,012,850	304,100	481,300	706,000
835.5	4,091,411	3,121,632	20,366,250	304,100	511,000	718,000
836.0	4,091,411	3,378,045	20,724,973	304,100	538,000	731,000
836.5	4,091,411	3,657,995	21,103,457	304,100	560,000	744,000
837.0	4,091,411	3,945,452	21,488,639	304,100	581,000	761,000
837.5	4,091,411	4,240,427	21,880,228	304,100	604,000	777,000
838.0	4,091,411	4,542,927	22,277,967	304,100	626,000	795,000
838.5	4,091,411	4,868,144	22,684,794	304,100	650,000	810,000
839.0	4,091,411	5,200,592	23,095,603	304,100	682,000	823,000
839.5	4,091,411	5,540,912	23,510,114	304,100	705,000	834,000
840.0	4,091,411	5,889,745	23,928,082	304,100	732,000	846,000
840.5	4,091,411	6,268,822	24,349,506	304,100	760,000	853,000
841.0	4,091,411	6,655,128	24,774,109	304,100	784,000	860,000
841.5	4,091,411	7,049,047	25,201,772	304,100	808,000	868,000
842.0	4,091,411	7,450,979	25,632,372	304,100	831,000	875,000
842.5	4,091,411	7,879,514	26,066,229	304,100	855,000	882,000
843.0	4,091,411	8,316,596	26,502,750	304,100	880,000	890,000
843.5	4,091,411	8,762,626	26,941,945	304,100	904,000	899,000
844.0	4,091,411	9,218,008	27,384,013	304,100	931,000	909,000
844.5	4,091,411	9,692,452	27,829,546	304,100	948,000	918,000
845.0	4,091,411	10,172,779	28,278,292	304,100	962,000	927,000
845.5	4,091,411	10,659,065	28,730,361	304,100	975,000	936,000
846.0	4,091,411	11,151,404	29,185,855	304,100	988,000	945,000
846.5	4,091,411	11,652,757	29,645,829	304,100	1,003,000	955,000
847.0	4,091,411	12,160,557	30,109,510	304,100	1,017,000	964,000
847.5	4,091,411	12,674,872	30,576,987	304,100	1,030,000	974,000
848.0	4,091,411	13,195,774	31,048,346	304,100	1,044,000	985,000
848.5	4,091,411	13,724,465	31,534,080	304,100	1,058,000	996,000
849.0	4,091,411	14,259,242	32,023,612	304,100	1,071,000	1,008,000
849.5	4,091,411	14,800,183	32,517,015	304,100	1,084,000	1,023,000
850.0	4,091,411	15,347,364	33,014,397	304,100	1,096,000	1,040,000
850.5	4,091,411	15,902,340	33,517,598	304,100	1,110,000	1,051,000
851.0	4,091,411	16,463,011	34,025,340	304,100	1,121,000	1,063,000
851.5	4,091,411	17,029,425	34,538,001	304,100	1,132,000	1,075,000
852.0	4,091,411	17,601,633	35,055,618	304,100	1,145,000	1,089,000

Table A- 2: Tenas Control Pond Stage-Storage-Elevation Relationship

Elevation [masl]	Cuml. Volume [m ³]	Surface Area [m ²]
785.5	-	-
786.0	87	202
786.5	534	837
787.0	1,321	1,751
787.5	2,541	3,043
788.0	4,450	5,052
788.5	8,418	9,207
789.0	14,799	15,886
789.5	24,228	21,913
790.0	36,986	29,776
790.5	55,181	38,774
791.0	77,681	49,509
791.5	105,167	59,643
792.0	137,796	71,412
792.5	178,238	83,315
793.0	224,187	96,529
793.5	275,891	108,818
794.0	333,501	122,351
794.5	399,936	135,701
795.0	472,619	150,138
795.5	551,708	164,821
796.0	637,362	180,687
796.5	733,838	195,054
797.0	836,404	210,125
797.5	945,189	224,448
798.0	1,060,335	239,564
798.5	1,187,144	256,691
799.0	1,321,141	274,806
799.5	1,462,424	290,253
800.0	1,611,092	306,428

Table A- 3: Pit Lake Stage-Volume Relationship

Elevation [masl]	Volume [m³]	Elevation [masl]	Volume [m³]	Elevation [masl]	Volume [m³]
823	-	861	703,627	899	4,817,737
824	1,013	862	740,918	900	5,031,452
825	3,080	863	779,333	901	5,252,152
826	6,375	864	819,038	902	5,478,455
827	10,887	865	860,129	903	5,710,202
828	16,526	866	902,719	904	5,947,304
829	23,203	867	947,026	905	6,189,626
830	30,886	868	993,339	906	6,437,193
831	39,526	869	1,041,923	907	6,689,938
832	49,059	870	1,095,005	908	6,947,581
833	59,429	871	1,153,134	909	7,209,925
834	70,600	872	1,214,687		
835	82,554	873	1,279,964		
836	95,292	874	1,349,137		
837	108,821	875	1,422,472		
838	123,122	876	1,500,607		
839	138,177	877	1,583,875		
840	153,974	878	1,672,615		
841	170,595	879	1,766,753		
842	187,854	880	1,866,647		
843	205,785	881	1,972,436		
844	224,453	882	2,083,348		
845	243,890	883	2,199,315		
846	264,108	884	2,320,391		
847	285,126	885	2,446,467		
848	306,981	886	2,577,434		
849	329,726	887	2,713,361		
850	354,571	888	2,854,404		
851	381,678	889	3,000,718		
852	409,754	890	3,155,048		
853	438,772	891	3,317,654		
854	468,710	892	3,485,835		
855	499,551	893	3,659,558		
856	531,296	894	3,838,809		
857	563,937	895	4,023,575		
858	597,486	896	4,213,854		
859	631,936	897	4,409,654		
860	667,315	898	4,610,917		